



Sai Ashram

Nehru Bal Sadan

Society Reg. No. MAH-637/93 (Nagpur), Public Trust Reg. No. : F-11104 (Nagpur)
C/o Nehru Bal Sadan, Opp. Plot No. U-87, M.I.D.C. Hingna Road, Nagpur
Tel. No. : 07104-242857 | E-mail : nehrubalsadan27@gmail.com



TENDER NOTICE

SAI ASHRAM (NEHRU BAL SADAN) Invites Sealed Tenders on item rate basis from well reputed established contractors having experience in relevant field to undertake following jobs:-

Sr. No	Description of Work	(Approx. Amount) in Rs.
1	CONSTRUCTION OF FRONT COMPOUND WALL AND PROVIDING AND FIXING OF GRILLS AT VARIOUS LOCATION AT SAI ASHRAM, MIDC, HINGNA ROAD, NAGPUR (M.H)	Rs.15,000,00 /-*

(In Rupee FIFTEEN LAKHS only)

Contact details:-Mr. Yogiraj Nashikwar (Mob.):+91 9518920324 at Atrey Layout, Nagpur during office hours on all working days.

Tenders will be available for sale from 18.12.2021 to 22.12.2021 between 10:00 Hours To 17:30 Hours.

Tender Opening date: 24.12.2021 at 15:30 hours

SD
Secretary

ESTIMATE

NAME OF WORK = Construction Of Compound Wall at Sai Asram MIDC Hingna Road , Nagpur.

SR. NO.	DESCRIPTION	QTY	RATE	PER	AMOUNT
1	Dismantling work Dismantling of RCC work including disposal of material etc. complete	9		CUM	
2	Dismantling work Dismantling brick masonry in cement mortar and stacking the materials as directed etc. complete.	37.26		CUM	
3	Providing and casting in situ cement concrete of required grade of trap / granite / gneiss / quartzite metal for R.C.C. pardi 50 to 150 mm thick including steel centering, plywood /steel formwork, compaction, finishing uneven and honeycombed surface with C.M. 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening them if special finish is to be provided and curing etc. Complete.(Excluding reinforcement, including cover block) The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only.(Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc.) (Wooden centering will not be allowed) R.C.C.M-20 PARDI	27		CUM	

4	<p>Providing and casting in situ cement concrete of required grade of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed design and drawings or as directed, including steel centering, plywood/steel formwork, compaction, finishing uneven and honeycombed surface with C.M. 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing etc. complete. Including use of plasticizer wherever necessary as directed by Engineer (Excluding reinforcement, including cover block). The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed) R.C.C.M-20 COLUMN</p>	4.14		CUM	
5	<p>Providing sand faced plaster for external portion in cement mortar using Kharsalia / Kasaba or similar type of sand, in all positions including base coat of 15 mm. Thick in C.M. 1:4 using water proofing compound at 1 kg per cement bag, curing the same for not less than 3 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in C.M. 1:4 finishing the surface by taking out grains, making grooves and curing for fourteen days scaffolding etc. complete.</p>	360		SQM	
6	<p>Providing and applying Birla white cement of approved color and shade in two coats to new surface including scaffolding and preparing the surface by brushing and brooming down (including base coat of white wash) etc. complete.</p>	360		SQM	

7	Fixing in position reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams and columns, canopies, staircases, newels, chajjas, lintels, pardies, coping, fins, arches etc. as per detailed design and drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed.FOR TMT STEEL	2		MT	
8	Providing Cement Bags	300		NOS	
9	Providing Reinforcement	2		MT	
			Total Amount =		